## TOWN OF PRATTSVILLE Office of Code Enforcement 14517 Main Street Prattsville, NY 12468 (518) 299-3051 ext4

## **REQUIRED INSPECTIONS FOR GENERAL CONSTRUCTION**

WORK SITE prior to the issuance of a Building Permit
FOOTING After forming and installation of steel, but before pouring concrete.
FOUNDATION After damp-proofing and before backfilling. Reinforcement prior to pouring concrete
UTILITIES Prior to backfilling or covering up any part of a water line, sewer line, septic system or footing drain. (The Building Department only inspects the interior water lines.)
<ul> <li>FRAMING After rough plumbing installation, all drain, waste and vent piping must be tested. Heating duct work/piping and all electrical work must be inspected prior to insulation.</li> <li>All interior water lines prior to covering/backfilling</li> <li>Submission of (2) sets of stamped certified truss specifications <b>prior</b> to framing.</li> <li>Foundation location prior to framing.</li> </ul>
J Cales. shall be provided prior to framing inspection.
DUCTWORK Rough-in ductwork in place and sealing of all joints <u>prior</u> to covering.
DUCT BLASTER test on ductwork if needed prior to framing inspection.
DUCT PRESSURE TEST required if ducts outside of thermal envelope (IECC.R403:3.3)
<ul> <li>HEAT PRODUCING APPLIANCES Furnaces, water heaters, and fireplaces must be inspected and approved. Any concealed piping or vents must be inspected prior to insulation inspection.</li> <li>INSULATION Prior to sheetrocking or covering any insulation.</li> </ul>
INSULATE All mechanical and plumbing system piping, <sup>3</sup> / <sub>4</sub> " or larger, capable of carrying fluids above 105 <sup>O</sup> or below 55 deg (IECC R403.4)
must be insulated to a minimum of R-3 if prescriptive compliance used (Rescheck)
SMOKE/CARBON MONOXIDE DETECTORS When required by NYS Code.
BLOWER DOOR TESTING BY approved third party for compliance with ASTME 779 and E 1827.
FINAL When project is completed, including final electrical inspection by third party and heat producing appliances. Inspection and approvals from and involved agencies will be required if applicable. <u>An energy code</u> certification sticker shall be posted on or in the electrical distribution panel.
OTHER Under normal circumstances, your Certificate of Occupancy document will be prepared within forty- eight (48) hours after completion of all of the above.
IT IS ILLEGAL TO OCCUPY ANY BUILDING WITHOUT A CERTIFICATE OF OCCUPANCY (IN VIOLATION OF THE
CODE OF THE TOWN OF PRATTSVILLE). Section 7 of the Town of Prattsville local law #2.
Building permit applicant is responsible for scheduling the indicated inspections.

- Additional inspections may be required by circumstances, or by the inspector, based on results of above inspections.
- A twenty-four (24) hour advance notice is required to schedule all inspections.

No inspections will be performed unless the building permit card is visible from the Code Enforcement Officer